Insured:	Mrs Louisa Scarr	Cell:	00000000000
Home:	1 Riverside Cottages The Dean Alresford SO24 9BE		
Claim Handler:	Davies		
Surveyor:	Davies		

Claim Reference: 90964727181 **Policy Reference:** Z11838455/001 **Peril:** Escape Of Water

Date Contacted:	05/03/2025 09:30		
Loss Date:	01/03/2025 00:00	Date Received:	05/03/2025 00:00
Date Inspected:	08/03/2025 09:00	Date Entered:	05/03/2025 16:31
Date Est. Completed:	17/09/2025 10:45		

Price List:	ENMDRESJAN25_EP Restoration/Repair/Refurbish
Estimate:	MRS_LOUISA_SCARR

MRS_LOUISA_SCARR

SKETCH1

Main Level

Main Level

DESCRIPTION	QTY
11. Storage Per Week Per Cubic Meter	168.00 M3
Based on 4 crates for 6 weeks	
14. Storage Per Week Per Cubic Meter	336.00 M3
For additional storage (not including the first 6 weeks) for 4x crates for an additional 12 weeks up to 17/09/2025	
13. PC Sum - Removal of contents in and out (subject to quote) Evidence to be supplied	1.00 EA
PC sum for contents pack, removal to storage and return	

NOTES:



Lounge/hallway **Height: 2.23 m**

57.04 M2 Walls	34.62 M2 Ceiling
91.66 M2 Walls & Ceiling	34.62 M2 Floor
25.58 LM Ceil. Perimeter	25.58 LM Floor Perimeter

DESCRIPTION	QTY
6. Air Mover 1-21 days	42.00 EA
Allow for 2 x air mover for 21 days	
7. Desiccant Dehum by day – Large - 1-21 DAYS INC	21.00 DA
Allow for 1x desiccant dehumidifier for 21 days	
8. Anti-microbial by Sq M	34.62 M2
Allow for decontamination of affected area	
15. Air Mover 22-42	42.00 EA
16. Desiccant Dehum by day – Large - 22-42 DAYS INC	21.00 DA

NOTES:



Kitchen utility **Height: 2.18 m**

57.64	M2 Walls	42.15	M2 Ceiling
99.79	M2 Walls & Ceiling	42.15	M2 Floor
26.44	LM Ceil. Perimeter	26.44	LM Floor Perimeter

DESCRIPTION	QTY
1. Air Mover 1-21 days	42.00 EA
Allow for 2x air mover for 21 days	
2. Dehum by day Large Refrigerant - 1-21 DAYS INC	21.00 DA
Allow for 1x refrigerant dehumidifier for 21 days	
3. Anti-microbial by Sq M	42.15 M2
Allow for decontamination of area	
4. Re-visit & Moisture Reading Survey per visit - Fixed Price	3.00 EA
Allow for re visits during drying period for moisture readings	
5. First Hours Labour For Leading Tech Only	1.00 EA
Allow for set up drying equipment	
17. Dehum by day Large Refrigerant - 22-42 DAYS INC	21.00 DA
18. Air Mover 22-42	42.00 EA

NOTES:



W/c **Height: 2.21 m**

11.58	M2 Walls	1.53	M2 Ceiling
13.11	M2 Walls & Ceiling	1.53	M2 Floor
5.24	LM Ceil. Perimeter	5.24	LM Floor Perimeter

DESCRIPTION	QTY
9. Air Mover 1-21 days	21.00 EA
Allow for 1x air mover for 21 days	
10. Anti-microbial by Sq M	1.53 M2
Allow for decontamination of affected area	
19. Air Mover 22-42	21.00 EA

CONTINUED - W/c

DESCRIPTION	QTY

NOTES:

Grand Total Areas:

126.26	M2 Walls	78.31	M2 Ceiling	204.57	M2 Walls and Ceiling
78.31	M2 Floor	0.00	M2 Short Wall	57.26	LM Floor Perimeter
0.00	M2 Long Wall			57.26	LM Ceil. Perimeter
78.31	Floor Area	83.24	Total Area	126.26	Internal Wall Area
94.54	External Wall Area	41.00	External Perimeter of Walls		
0.00	Surface Area	0.00	Total Hip Length	0.00	Total Perimeter Length
0.00	Total Ridge Length				