QUOTE

Mr Nicholas Scarr
1 Riverside Cottages
The Dean
Alresford
Hampshire
SO24 9BE
GBR

Date
19 Dec 2025

Expiry
15 Jan 2026

Quote Number
QU-2730

Reference
Preparation Works

VAT Number
241743519

Silk Services Limited
Wood Farm
Bramdean
Alresford
SO24 0JH
01962 771815
info@silkservices.co.uk
www.silkservices.co.uk

Preparation Works For McLennan

Dear Nicholas,

Thank you for your valued enquiry and instruction to quote for the above project.

I am pleased to attach the following quotation as requested. Should you have any questions regarding this, please do not hesitate to contact me.

Considerations:

This quotation is based on the specification described herein. Any changes to drawings or specification would be treated as a variation and may be subject to an agreed price adjustment.

This estimate is valid for a period of 28 days from date of issue.

Trusting I have interpreted your requirements correctly as every effort has been made to accurately quote for your project.

I look forward to hearing from you.

Yours sincerely
Jason Silk
Silk Services Ltd.

Description	Quantity	Unit Price	VAT	Amount GBP
Brief of works: The proposed works are critical enabling works that must be completed prior to the commencement of third party contractor activities. They are required to address existing site constraints and without completion of these works, the third-party contractor would be unable to perform their contracted scope.				
To supply and install cementicious fairing coat to perimeter of ground floor as per McLennan's drawing No: 001 - Project No: 30114. Using a 3:1 ratio of washed sharp sand and cement to provide a smooth surface for others to apply to.	1.00	6,630.00	20%	6,630.00

Description	Quantity	Unit Price	VAT	Amount GBP
Installation of Linear Surface Drainage at Rear Elevation Scope: To supply and install an ACO linear channel drain across the rear threshold beneath the French doors. The drain will be connected directly to the external sump pump chamber to form part of the active water management system. Purpose and Justification: This channel drain forms an integral part of the waterproofing and pressure-relief strategy. It intercepts surface and ground water, reducing hydrostatic pressure at the building perimeter. This is essential to protect the structure from recurrence of water ingress and to allow the internal waterproofing system (Type C) to operate within designed capacity. The component is part of a BS 8102-compliant combined system and directly supports the performance of both internal and external pump chambers.	1.00	5,996.00	20%	5,996.00

Payment Terms:
5% Deposit on acceptance of quotation.
50% 1st stage payment 4 weeks prior to agreed start date.
25% 2nd stage payment once internal rendering has been completed.
Balance on completion of works.

Subtotal	12,626.00
TOTAL VAT 20%	2,525.20
TOTAL GBP	**15,151.20**

Terms

For our full terms and conditions please visit our website @ www.silkservices.co.uk.
Quotes are valid for 28 days from point of issue.

SILK SERVICES RESERVE THE RIGHT TO PASS ON ANY UNFORESEEN SUPPLY CHAIN INCREASES.

Once you are happy with your quotation please click on the accept button to confirm.