SCOPE OF WORKS

Claim Number:	90964727158	**Date:**	19/03/2025 12:20
Insured Name:	Louisa Scarr & Nicholas Scarr		
Address:	1 Riverside Cottages The Dean Alresford Hampshire SO24 9BE		

REPAIR BREAKDOWN

External Repairs

External 1 - Front/rear%20gardens

Description	Unit Type	Units
NL492305: Non listed > Item Sanatize the front and rear of the property	Per Item	1.00

Internal Repairs

Room 1 - Dining kitchen

Room Shape: Rectangle
Room Dimensions (main area):
Length: 6.36 m
Width: 5.37 m
Height: 2.18 m
Floor/Ceiling Area: 34.15 m²
Room Perimeter: 23.46 m
Wall Area: 51.14 m²

Description	Unit Type	Units
DW02: Dayworks > All Trades Carpenter (Hourly rate)	Per Item	8.00
DW06: Dayworks > All Trades Operative/Labourer (Hourly rate)	Per Item	8.00
DE24: Decorating > Wooden surfaces Prepare undercoat and gloss skirting up to 150mm girth.	Per Lin m	16.00
FL11: Flooring > Remove Floor coverings only Lift remove and dispose of floor covering (Laminate, Real Wood or Parquet) including underlay and trims	Per m²	31.00
FL15: Flooring > Solid timber flooring Renew existing solid timber flooring including trims and underlay to match pre-existing - PC materials allowance > ?45 per m2	Per m²	31.00
FL31: Flooring - strip out > Skirting Remove and dispose or set aside for re-use of skirtings, any depth	Per m²	16.00
JO17: Joinery > Kitchen - Refit previously set aside Double base unit 1000 x 600 - Refit previously set aside	Per Item	4.00
JO50: Joinery > Kitchen - Refit previously set aside Plinth - Refit previously set aside	Per Lin m	6.00
JO19: Joinery > Kitchen - Remove & set aside for reuse Double base unit 1000 x 600 - Remove & set aside for reuse	Per Item	4.00
JO52: Joinery > Kitchen - Remove & set aside for reuse Plinth - Remove & set aside for reuse	Per Lin m	6.00
JO85: Joinery > Skirting Supply & fix skirting varying profiles maximum depth 150mm.	Per Item	16.00
PR07: Preliminaries > Debris removal and boarding/sheeting up MEGABAG (1.5 cubic yards, up to 1.5 tonnes) - Collect loose general debris and remove from site.	Per Item	1.00
WG01: White Goods > Remove & Set aside or dispose Remove and set aside white goods	Per Item	3.00

WG02: White Goods > Replace previously set aside Replace white goods	Per Item	3.00

Room 2 - Lounge/hallway%20

Room Shape: L-Shaped
Room Dimensions (main area):
Length: 6.10 m
Width: 4.30 m
Height: 2.20 m
Room Dimensions (additional area):
Length: 3.90 m
Width: 2.80 m
Floor/Ceiling Area: 37.15 m²
Room Perimeter: 28.60 m
Wall Area: 62.92 m²

Description	Unit Type	Units
DW02: Dayworks > All Trades Carpenter (Hourly rate)	Per Item	8.00
DE03: Decorating > Walls Apply mist coat of emulsion to new wall plaster	Per m²	13.00
DE27: Decorating > Walls WALLS - Prepare and apply two coats of emulsion to existing painted or papered surfaces.	Per m²	40.00
DE39: Decorating > Walls WALLS - Strip existing wall coverings, prepare, size and hang embossed/woodchip or patterned wallpaper >?40 per roll	Per m²	18.00
DE24: Decorating > Wooden surfaces Prepare undercoat and gloss skirting up to 150mm girth.	Per Lin m	23.00
FL11: Flooring > Remove Floor coverings only Lift remove and dispose of floor covering (Laminate, Real Wood or Parquet) including underlay and trims	Per m²	23.00
FL15: Flooring > Solid timber flooring Renew existing solid timber flooring including trims and underlay to match pre-existing - PC materials allowance > ?45 per m2	Per m²	37.00
FL31: Flooring - strip out > Skirting Remove and dispose or set aside for re-use of skirtings, any depth	Per m²	23.00
JO63: Joinery > Boxing In Replace Boxing-In pipework etc. any girth.	Per m²	7.00
JO85: Joinery > Skirting Supply & fix skirting varying profiles maximum depth 150mm.	Per Item	23.00
JO93: Joinery - strip out > Boxing In Remove and dispose or set aside for re-use of pipe boxing - any girth	Per m²	7.00
PL05: Plastering > Walls Hack off loose and defective plaster, bag and remove rake out and prepare	Per m²	13.00
PL07: Plastering > Walls Plaster, float and set 2 coats plasterwork to walls	Per Item	13.00
PL21: Plastering > Walls Take down plasterboard to wall, de-nail stud cut and fix new plasterboard to wall and skim finish (gypsum products to be bagged)	Per m²	1.00
PR07: Preliminaries > Debris removal and boarding/sheeting up MEGABAG (1.5 cubic yards, up to 1.5 tonnes) - Collect loose general debris and remove from site.	Per Item	1.00

Davies Group Ltd, Wing A, 2 The Parklands, Bolton BL6 4SE
Company No. 06972457 VAT No. 328 1867 81
www.davies-group.com