From: Nicholas Scarr <nscarr@quantlogic.com>
To: Andy Lyne <Andy.Lyne@qlaims.com>
CC: Claims <Claims@qlaims.com>, Louisa Scarr <scarrlouisa@gmail.com>
Date: Monday 22 December 2025 at 09:50
Subject: Re: Qlaim 1816 N Scarr Re: Waterproofing Quotes from Maclennans and Silks -

Hi Andy,

I have discussed the reinstatement quote with Jason. As he was out of the office for most of last week, I asked him to prioritise isolating the waterproofing element, as this is the first activity on the critical path.

I have just called their office and they are closed until 5 January. The last position agreed with Jason was that Silks would be in a position to commence the waterproofing works on 5 January, subject to insurers' approval. This stage is a prerequisite to the wider reinstatement works, as Maclennans are unable to start until the waterproofing has been completed.

Any delay to approval or commencement of the waterproofing works will therefore have a direct knock-on impact on the overall programme and reinstatement timeline.

I will chase the full reinstatement quotation immediately once they are back in the office.

Best regards,

Nicholas

Nicholas Scarr
Sent from my iPhone

On 22 Dec 2025, at 08:14, Andy Lyne <Andy.Lyne@qlaims.com> wrote:

■

Morning Nick,

Just to confirm, those costs have been submitted for approval.

When are we likely to see the amended reinstatement quote? I recall you said they were amending it.

Best regards

Andy Lyne

Qlaims Adjuster

Mob: +44 (0) 7887522332

Qlaims Limited

Level 30, The Leadenhall Building

122 Leadenhall Street

London EC3V 4AB

Qlaims.com

Connect with us on LinkedIn to keep up to date with our evolving claims products and services – our Qlaims Insurance and Qlaimstech is really making a difference to the way Clients' claims are handled!

Authorised and regulated by the Financial Conduct Authority under firm reference number 775237. Registered Office Level 30, The Leadenhall Building, 122 Leadenhall Street, London EC3V 4AB. Registered in England No: 10650346.

The information in this email is confidential and intended solely for the addressee. Access by any other person to this email is not authorised. If you are not the intended recipient,

please delete this email. Any disclosure of this email or of the parties to it, any copying, distribution or any action taken or omitted to be taken in reliance on it is prohibited and may be unlawful.

We have updated our

Privacy Policy to align with the General

Data Protection Regulation. All our communications are also compliant with the Privacy and Electronic Communications Regulation

From: Nicholas Scarr <nscarr@quantlogic.com>

Sent: 19 December 2025 17:36

To: Andy Lyne <Andy.Lyne@qlaims.com>; Claims <Claims@qlaims.com>

Cc: Claims <Claims@qlaims.com>; Louisa Scarr <scarrlouisa@gmail.com>

Subject: Waterproofing Quotes from Maclennans and Silks -

Dear Andy,

I'm writing to clarify the necessity and function of the sump pump systems and battery backup specified within the proposed waterproofing scheme for 1 Riverside Cottages, and to confirm their inclusion within the waterproofing design as reflected in the MacLennan

quotation, with associated builder's works addressed in the Silks quotation.

Due to the property's construction — including earth-retaining walls, raised external ground levels, and underlying clay subsoil — the structure is subject to persistent hydrostatic pressure and perched groundwater. This creates a foreseeable risk of water

ingress at slab joints and wall–floor interfaces, particularly following rainfall or infrastructure failure, as occurred during the February 2025 flooding event.

The MacLennan proposal specifies:

An internal Hydrosump-Pro to manage water collected behind the internal cavity drain membrane (Type C protection);

An external Hydrosump-Pro to relieve water build-up around the structure, particularly at the rear terrace threshold.

Because flood events often coincide with power failure — notably in this case due to Southern Water's pumping station malfunction — the design also includes battery backup systems (Victron inverter + dual battery banks). These ensure continued pump operation

during mains outages.

This configuration complies with BS 8102:2022, which requires drained systems to remain functional under foreseeable conditions, including power loss (Clause 9.2.3). Duty and backup pumps, high-level alarms, and battery-supported operation are all standard

requirements for resilient protection in such environments.

The Silks quotation has been prepared following detailed discussions with MacLennan and reflects the builder-side works required to support delivery of the waterproofing system as specified.

Please find attached both the MacLennan and Silks quotations for reference.

To summarise: the sump pumps and battery backup are not discretionary. They are essential elements of a BS-compliant waterproofing strategy, addressing known risks at this property. Their inclusion is necessary to ensure the system performs as designed under

both normal and adverse conditions.

Kind regards,

Nicholas

Nicholas Scarr

E&OE, this email and any files transmitted with it are confidential and intended solely for the use of the individual or entity to whom they are addressed. If you have received this

email in error please notify the system manager.