Insured:	Mrs Louisa Scarr	Cell:	(000) 000-0000
Home:	1 Riverside Cottages The Dean Alresford SO24 9BE		
Claim Handler:	Tommy Fuller	E-mail:	tommyf@topmarx.co.uk
Business:	Chardan House Culverlands Business Park Winchester Shedfield, Hampshire SO32 2JF		
Surveyor:	Tommy Fuller	E-mail:	tommyf@topmarx.co.uk
Business:	Chardan House Culverlands Business Park Winchester Shedfield, Hampshire SO32 2JF		

Claim Reference: 90964727133 **Policy Reference:** Z11838455/001 **Peril:** Escape Of Water

Date Contacted:	16/04/2025 14:33		
Loss Date:	01/03/2025 00:00	Date Received:	15/04/2025 23:00
Date Inspected:	16/04/2025 14:33	Date Entered:	16/04/2025 08:17
Date Est. Completed:	23/04/2025 14:34		

Price List:	ENSEDAVS25B_EP Restoration/Repair/Refurbish
Estimate:	MRS_LOUISA_SCARR

MRS_LOUISA_SCARR

Main Level



Kitchen **Height: 2.44 m**

57.40	M2 Walls	34.38	M2 Ceiling
91.78	M2 Walls & Ceiling	34.38	M2 Floor
23.54	LM Ceil. Perimeter	23.54	LM Floor Perimeter

DESCRIPTION	QTY
51. Fridge/Freezer - Freestanding - Remove & refit	1.00 EA
44. Remove Radiator - Single panel - Up to 600H x 801-1000L	1.00 EA
45. Remove Architrave - Softwood - 50mm - Chamfered/bullnose	5.00 LM
46. Remove Plaster - Lightweight gypsum - Two coat - 12mm	23.54 M2
47. Remove Engineered wood flooring	34.38 M2
48. Remove Skirting - Softwood - 150mm - Moulded	23.54 LM
49. Joiner - 2nd Fixing - Per hour	32.00 HR
x 2 trades for two days to carefully dismantle the kitchen	
50. Remove Worktop - Laminated - 40mm - 620mm deep	2.00 LM
54. Dishwasher - Freestanding - Remove & refit	1.00 EA
58. Remove Base unit - 800mm w/drawer/doors	10.00 EA
59. Remove Worktop - Laminated - 40mm - 620mm deep - High grade	8.00 LM
53. Plumber - Gas Safe Engineer - Per hour	8.00 HR
To disconnect and set aside auger	
60. Kitchen sink - 1.0 bowl - Remove & refit	1.00 EA

NOTES:



Utility Room **Height: 2.44 m**

19.56	M2 Walls	3.99	M2 Ceiling
23.55	M2 Walls & Ceiling	3.99	M2 Floor
8.02	LM Ceil. Perimeter	8.02	LM Floor Perimeter

DESCRIPTION	QTY

CONTINUED - Utility Room

DESCRIPTION	QTY
12. Remove Radiator - Single panel - Up to 600H x 801-1000L	1.00 EA
27. Remove Larder unit - Up to 600 x 2110mm	1.00 EA
15. Remove Architrave - Softwood - 50mm - Chamfered/bullnose	5.00 LM
18. Remove Plaster - Lightweight gypsum - Two coat - 12mm	8.02 M2
16. Remove Engineered wood flooring	3.99 M2
13. Remove Skirting - Softwood - 150mm - Moulded	8.02 LM
29. Joiner - 2nd Fixing - Per hour	4.00 HR
to allow for removing and setting aside larder unit and worktop	
28. Remove Worktop - Laminated - 40mm - 620mm deep	2.00 LM

NOTES:



Cloakroom **Height: 2.44 m**

13.26	M2 Walls	1.73	M2 Ceiling
15.00	M2 Walls & Ceiling	1.73	M2 Floor
5.44	LM Ceil. Perimeter	5.44	LM Floor Perimeter

DESCRIPTION	QTY
20. Toilet/WC pan & cistern - Remove & refit	1.00 EA
21. Pedestal and basin - Remove & refit	1.00 EA
22. Remove Radiator - Single panel - Up to 600H x 801-1000L	1.00 EA
23. Remove Architrave - Softwood - 50mm - Chamfered/bullnose	5.00 LM
24. Remove Plaster - Lightweight gypsum - Two coat - 12mm	5.44 M2
25. Remove Engineered wood flooring	1.73 M2
26. Remove Skirting - Softwood - 150mm - Moulded	5.44 LM

NOTES:



Lounge **Height: 2.44 m**

48.96	M2 Walls	23.26	M2 Ceiling
72.23	M2 Walls & Ceiling	23.26	M2 Floor
20.08	LM Ceil. Perimeter	20.08	LM Floor Perimeter

DESCRIPTION	QTY
30. Remove Radiator - Single panel - Up to 600H x 801-1000L	2.00 EA
31. Remove Architrave - Softwood - 50mm - Chamfered/bullnose	5.00 LM
32. Remove Plaster - Lightweight gypsum - Two coat - 12mm	20.08 M2
33. Remove Engineered wood flooring	23.26 M2
34. Remove Skirting - Softwood - 150mm - Moulded	20.08 LM

NOTES:



Hallway **Height: 2.44 m**

34.53	M2 Walls	11.68	M2 Ceiling
46.21	M2 Walls & Ceiling	11.68	M2 Floor
14.16	LM Ceil. Perimeter	14.16	LM Floor Perimeter

DESCRIPTION	QTY
39. Remove Radiator - Single panel - Up to 600H x 801-1000L	1.00 EA
40. Remove Architrave - Softwood - 50mm - Chamfered/bullnose	5.00 LM
41. Remove Plaster - Lightweight gypsum - Two coat - 12mm	14.16 M2
42. Remove Engineered wood flooring	11.68 M2
43. Remove Skirting - Softwood - 150mm - Moulded	14.16 LM
61. Remove Wallpaper	34.53 M2

NOTES:



enablings **Height: 2.44 m**

39.01	M2 Walls	16.00	M2 Ceiling
55.01	M2 Walls & Ceiling	16.00	M2 Floor
16.00	LM Ceil. Perimeter	16.00	LM Floor Perimeter

DESCRIPTION	QTY
35. Surface protection - Leak-proof drop cloth	15.00 M2
36. Skip - 6 cubic yards - Per load	3.00 EA
37. Electrical test - Full - Residential	1.00 EA
38. Electrician - Per hour	4.00 HR
to install a temp board	

NOTES:

Grand Total Areas:

212.73	M2 Walls	91.05	M2 Ceiling	303.78	M2 Walls and Ceiling
91.05	M2 Floor	0.00	M2 Short Wall	87.24	LM Floor Perimeter
0.00	M2 Long Wall			87.24	LM Ceil. Perimeter
91.05	Floor Area	98.21	Total Area	212.73	Internal Wall Area
139.82	External Wall Area	55.08	External Perimeter of Walls		
0.00	Surface Area	0.00	Total Hip Length	0.00	Total Perimeter Length
0.00	Total Ridge Length				